Dielectric Safety Testing & Inspection Process – Insulating Line Hose

This method ensures the preservation of the integrity of the line hoses, ensuring they are ready for subsequent testing procedures without compromising their structural integrity.

Eliminates all traces of streaks, stains, dirt, dust, oils, and other contaminants that may compromise the insulation properties of the line hoses.

Comprehensive testing process ensures that each line hose meets the required standards for dielectric integrity and electrical safety.



1. Cleaning

2. Drip Dry



3. Dielectric Testing



4. Visual Inspection

5. Certification Stamp

6. Ship or Pickup

Pickup or efficient delivery of the tested line hose to the designated recipients, facilitating their prompt integration into their operations.

Each line hose is stamped with a unique serial number and includes essential information such as the proof test voltage, maximum use voltage, and the date of testing completion.

Scrutinize for signs of age cracking, cuts, depressions, embedded material, form marks, hard spots, mold marks, nicks, snags, scratches, ozone damage, and tears.

Get Your Line Hose Tested Every 12 Months
2 Week Turnarounds - Meets Standards of ASTM D1050/F478 - Accredited by NAIL and PET

Burlington Safety Laboratory Inc.

Burlington, NJ | Pleasanton, CA | Westminster, CA

www.burlingtonsafety.com info@burlingtonsafety.com (800) 220-2120 | (888) 817-1412 | (800) 296-2803